

§§ 250.507–250.508 [Reserved]

§ 250.509 Well-completion structures on fixed platforms.

Derricks, masts, substructures, and related equipment shall be selected, designed, installed, used, and maintained so as to be adequate for the potential loads and conditions of loading that may be encountered during the proposed operations. Prior to moving a well-completion rig or equipment onto a platform, the lessee shall determine the structural capability of the platform to safely support the equipment and proposed operations, taking into consideration the corrosion protection, age of platform, and previous stresses to the platform.

[53 FR 10690, Apr. 1, 1988, as amended at 54 FR 50616, Dec. 8, 1989. Redesignated at 63 FR 29479, May 29, 1998]

§ 250.510 Diesel engine air intakes.

No later than May 31, 1989, diesel engine air intakes shall be equipped with a device to shut down the diesel engine in the event of runaway. Diesel engines which are continuously attended shall be equipped with either remote operated manual or automatic-shutdown devices. Diesel engines which are not continuously attended shall be equipped with automatic-shutdown devices.

§ 250.511 Traveling-block safety device.

After May 31, 1989, all units being used for well-completion operations which have both a traveling block and a crown block shall be equipped with a safety device which is designed to prevent the traveling block from striking the crown block. The device shall be checked for proper operation weekly and after each drill-line slipping operation. The results of the operational check shall be entered in the operations log.

§ 250.512 Field well-completion rules.

When geological and engineering information available in a field enables the District Supervisor to determine specific operating requirements, field well-completion rules may be established on the District Supervisor's ini-

tiative or in response to a request from a lessee. Such rules may modify the specific requirements of this subpart. After field well-completion rules have been established, well-completion operations in the field shall be conducted in accordance with such rules and other requirements of this subpart. Field well-completion rules may be amended or canceled for cause at any time upon the initiative of the District Supervisor or upon the request of a lessee.

§ 250.513 Approval and reporting of well-completion operations.

(a) No well-completion operation shall begin until the lessee receives written approval from the District Supervisor. If completion is planned and the data are available at the time the Application for Permit to Drill, Form MMS-123 (see § 250.414 of this part), is submitted, approval for a well completion may be requested on that form. If the completion has not been approved or if the completion objective or plans have significantly changed, approval for such operations shall be requested on Form MMS-124, Sundry Notices and Reports on Wells.

(b) The following information shall be submitted with Form MMS-124 (or with Form MMS-123):

(1) A brief description of the well-completion procedures to be followed, a statement of the expected surface pressure, and type and weight of completion fluids;

(2) A schematic drawing of the well showing the proposed producing zone(s) and the subsurface well-completion equipment to be used;

(3) For multiple completions, a partial electric log showing the zones proposed for completion, if logs have not been previously submitted; and

(4) When the well-completion is in a zone known to contain H₂S or a zone where the presence of H₂S is unknown, information pursuant to § 250.417 of this part.

(c) Within 30 days after completion, Form MMS-125, Well Summary Report, including a schematic of the tubing and subsurface equipment, shall be submitted to the District Supervisor.

(d) Public information copies of Form MMS-125 shall be submitted in accordance with § 250.190.

[53 FR 10690, Apr. 1, 1988, as amended at 58 FR 49928, Sept. 24, 1993. Redesignated and amended at 63 FR 29479, 29485, May 29, 1998; 64 FR 72794, Dec. 28, 1999]

§ 250.514 Well-control fluids, equipment, and operations.

(a) Well-control fluids, equipment, and operations shall be designed, utilized, maintained, and/or tested as necessary to control the well in foreseeable conditions and circumstances, including subfreezing conditions. The well shall be continuously monitored during well-completion operations and shall not be left unattended at any time unless the well is shut in and secured.

(b) The following well-control-fluid equipment shall be installed, maintained, and utilized:

(1) A fill-up line above the uppermost BOP;

(2) A well-control, fluid-volume measuring device for determining fluid volumes when filling the hole on trips; and

(3) A recording mud-pit-level indicator to determine mud-pit-volume gains and losses. This indicator shall include both a visual and an audible warning device.

(c) When coming out of the hole with drill pipe, the annulus shall be filled with well-control fluid before the change in such fluid level decreases the hydrostatic pressure 75 pounds per square inch (psi) or every five stands of drill pipe, whichever gives a lower decrease in hydrostatic pressure. The number of stands of drill pipe and drill collars that may be pulled prior to filling the hole and the equivalent well-control fluid volume shall be calculated and posted near the operator's station. A mechanical, volumetric, or electronic device for measuring the amount of well-control fluid required to fill the hole shall be utilized.

§ 250.515 Blowout prevention equipment.

(a) The BOP system and system components and related well-control equipment shall be designed, used, maintained, and tested in a manner nec-

essary to assure well control in foreseeable conditions and circumstances, including subfreezing conditions. The working pressure rating of the BOP system and BOP system components shall exceed the expected surface pressure to which they may be subjected. If the expected surface pressure exceeds the rated working pressure of the annular preventer, the lessee shall submit with Form MMS-124 or Form MMS-123, as appropriate, a well-control procedure that indicates how the annular preventer will be utilized, and the pressure limitations that will be applied during each mode of pressure control.

(b) The minimum BOP system for well-completion operations shall include the following:

(1) Three preventers, when the expected surface pressure is less than 5,000 psi, consisting of an annular preventer, one preventer equipped with pipe rams, and one preventer equipped with blind or blind-shear rams.

(2) Four preventers, when the expected surface pressure is 5,000 psi or greater, or for multiple tubing strings consisting of an annular preventer, two preventers equipped with pipe rams, and one preventer equipped with blind or blind-shear rams. When dual tubing strings are being handled simultaneously, dual pipe rams shall be installed on one of the pipe-ram preventers.

(3) When tapered drill string is used, the minimum BOP system shall include either of the following:

(i) Four preventers, when the expected surface pressure is less than 5,000 psi, consisting of an annular preventer, two sets of pipe rams, one capable of sealing around the larger size drill string and one capable of sealing around the smaller size drill string (one set of variable bore rams may be substituted for the two sets of pipe rams), and one preventer equipped with blind or blind shear rams; or

(ii) Five preventers, when the expected surface pressure is 5,000 psi or greater, consisting of an annular preventer, two sets of pipe rams capable of sealing around the larger size drill string, one set of pipe rams capable of sealing around the smaller size drill string (one set of variable bore rams may be substituted for one set of pipe